



Ulta Beauty - Fresno DC
New RTUs Clarifications
850 E Central Avenue
11.11.2025

Walter,

Thank you for the opportunity to provide pricing for the cooling additions at Ulta's Fresno Distribution Center. The following budget is based on the addition of six (6) new RTUs to add 250 tons of cooling to eliminate hot zones in the warehouse.

-Brandon Clymer

Inclusions:

Division 01 General Conditions

1. Includes project management for duration.
2. Dumpsters and disposal in landfill.
3. Includes project supervision.
4. Temp Toilet facilities for workers for duration.

Division 05 Metal

1. Includes steel reinforcement for six new rooftop units.
2. Includes Structural Design.

Division 07 Thermal and Moisture Protection

1. Includes cutting of roof assembly for new RTUs.
2. Includes roofing and flashing of six roof top unit curbs.
3. Includes all roof stands and flashing required for electrical conduits run at roof level to new roof top units.

Division 21 Fire Suppression

1. Includes fire sprinkler allowance to accommodate new RTUs and HVLS fans.

Division 22 Plumbing

1. Includes allowance for condensate draining of six (6) RTUs. Drains to tie into existing plumbing system.
2. Includes associated mechanical design.

Division 23 HVAC

1. Includes four (4) new 50-ton and two (2) new 25-ton Fraser-Johnston RTUs and associated roof curbs.
 - a. Provides 250 tons of total additional cooling capacity.
 - b. Plenum returns.
2. Includes installation of ductwork and diffusers.
3. Includes Duct Sox to distribute air from the six (6) new RTU.



4. Includes crane to hoist and set new units.
5. Includes stand alone thermostats for each packaged unit.
6. Includes five (5) new HVLS fans.
7. Includes forty eight (48) air circulation fans.
8. Includes start up and commissioning.
9. Includes engineered mechanical design.

Division 26 Electrical

1. Power for new equipment will be pulled from existing main distribution panels.
2. Includes necessary breakers, panels and gear as needed for added HVAC equipment and fans.
3. Includes (2) new 600 amp electrical panels fed from existing Main Distribution Panels
4. Includes new home run power to six (6) new roof top units.
5. Includes six (6) non-fused disconnects at roof for new roof top units.
6. Includes power to (5) new HVLS fans.
7. Includes power for (48) circulation fans fed from available capacity in existing lighting and receptacle panels.
8. Includes fire alarm tie-in for new roof top units and HVLS fans.

Exclusions and Clarifications:

1. Pricing is based on preliminary drawings from HVAC design engineer.
2. Pricing is based on current structure having capacity to support new roof top equipment with supplemental reinforcement added to existing structural members.
3. Excludes additional electrical service. Assumes current electrical distribution panels have capacity to power units.
4. Excludes any BMS controls.
5. Excludes anything not specifically called out.
6. Project to be done during normal working hours.
7. Excludes costs for Fresno Permits. This will be a reimbursable expense if permits are required by the city.

End of Document