

SPECIAL INSPECTION:

THE FOLLOWING STRUCTURAL ELEMENTS OF CONSTRUCTION SHALL REQUIRE SPECIAL INSPECTION PER CBC SECTION 1704 AND 1705. OWNER TO FURNISH INSPECTION UNLESS INSTRUCTED OTHERWISE BY THE CONSTRUCTION CONTRACT. TEST RESULTS AND REPORTS SHALL BE FURNISHED TO ARCHITECT AND EOR WITHIN ONE WEEK OF TEST OR INSPECTION.

NOTES

1. SPECIAL INSPECTION IS NOT A SUBSTITUTE FOR INSPECTION BY A COUNTY INSPECTOR. SPECIALLY INSPECTED WORK WHICH IS INSTALLED OR COVERED WITHOUT THE APPROVAL OF THE COUNTY INSPECTOR IS SUBJECT TO REMOVAL OR EXPOSURE.
2. THE SPECIAL INSPECTORS MUST BE CERTIFIED BY THE COUNTY TO PERFORM THE TYPES OF INSPECTION SPECIFIED.
3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO INFORM THE SPECIAL INSPECTOR OR INSPECTION AGENCY AT LEAST ONE WORKING DAY PRIOR TO PERFORMING ANY WORK THAT REQUIRES SPECIAL INSPECTION. ANY WORK PERFORMED WITHOUT REQUIRED SPECIAL INSPECTION IS SUBJECT TO REMOVAL.
4. SUBMIT WRITTEN REPORTS WITHIN TWO DAYS OF TESTING TO ENGINEER OF RECORD AND BUILDING OFFICIAL.
5. SPECIAL INSPECTIONS ARE NOT A REPLACEMENT FOR A CONTRACTOR'S QUALITY ASSURANCE PROGRAM. THE CONTRACTOR MUST PROVIDE ALL REQUIREMENTS OF THE CONSTRUCTION DOCUMENTS.

SCHEDULE OF SPECIAL INSPECTIONS NOMENCLATURE

P - PERFORM THESE SPECIAL INSPECTIONS TASKS FOR EACH WELDED JOINT OR MEMBER. (AISC 360 AND AISC 341)

O - OBSERVE THESE SPECIAL INSPECTIONS ITEMS ON A RANDOM DAILY BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS. (AISC 360 AND AISC 341)

D - DOCUMENT, WITH A REPORT, THAT THE WORK HAS BEEN PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. (AISC 341)

QUALITY CONTROL (QC) INSPECTION TASKS SHALL BE PERFORMED BY THE FABRICATOR'S OR ERECTOR'S QUALITY CONTROL INSPECTOR, AS APPLICABLE, IN ACCORDANCE WITH AISC 360 SECTIONS N5.4, N5.6, N5.7, AND N5.8. TASKS IN STRUCTURAL STEEL SPECIAL INSPECTION TABLES LISTED FOR QC ARE THOSE INSPECTIONS PERFORMED BY THE QUALITY CONTROL INSPECTOR TO ENSURE THAT THE WORK IS PERFORMED IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS, WHICH INCLUDES SHOP DRAWINGS AND ERECTION DRAWINGS, CODES AND STANDARDS.

QUALITY ASSURANCE (QA) INSPECTOR SHALL REVIEW THE MATERIAL TEST REPORTS AND CERTIFICATIONS AS LISTED IN AISC 360 SECTIONS N5.4, N5.6, N5.7, AND N5.8. TASKS IN STRUCTURAL STEEL INSPECTION TABLES LISTED FOR QA ARE THOSE INSPECTIONS PERFORMED BY THE QUALITY ASSURANCE INSPECTOR TO ENSURE THAT THE WORK IS PERFORMED IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS. CONCURRENT WITH THE SUBMITTAL OF SUCH REPORTS TO THE AHJ, EOR, OWNER AND AOR, THE QUALITY ASSURANCE AGENCY SHALL SUBMIT INSPECTION REPORTS AND NONDESTRUCTIVE TESTING REPORTS TO THE FABRICATOR AND ERECTOR.

SCHEDULE NOTES

1. ITEMS IDENTIFIED WITH (AISC 341) IN THE TASK COLUMN ARE REQUIRED ONLY WHERE R > 3 (THE PROJECT IS DESIGNED PER AISC 341 – SEISMIC PROVISIONS FOR STRUCTURAL STEEL BUILDINGS).
2. * - INDICATES SPECIAL INSPECTIONS REQUIRED FOR WELD RESISTANCE IN THE FOLLOWING AREAS:
A. IN WIND EXPOSURE CATEGORY B, WHERE VASD IS 120 MILES PER HOUR OR GREATER.
B. IN WIND EXPOSURE CATEGORY C OR D, WHERE VASD IS 110 MILES PER HOUR OR GREATER.
3. ** - INDICATES SPECIAL INSPECTIONS REQUIRED FOR SEISMIC RESISTANCE IN THE FOLLOWING AREAS:
A. SEISMIC FORCE-RESISTING SYSTEMS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY C, D, E OR F.
B. DESIGNATED SEISMIC SYSTEMS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY C, D, E OR F.
C. MECHANICAL AND ELECTRICAL COMPONENTS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY C, D, E OR F.
D. STRUCTURAL COMPONENTS NOT PART OF EMERGENCY OR STANDBY POWER SYSTEMS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY E OR F.
E. STORAGE RACKS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY D, E OR F.
4. *** - INDICATES DOCUMENTATION ONLY REQUIRED FOR PROJECTS WHERE R > 3 (DESIGNED UNDER AISC 341). FOR PROJECTS ONLY DESIGNED UNDER AISC 360, REMOVE "D" DESIGNATION.
5. **** - INDICATES AT MOMENT AND BRACED FRAMES WHERE R > 3. FOLLOWING PERFORMANCE OF THIS INSPECTION TASK FOR TEN WELDS TO BE MADE BY A GIVEN WELDER, WITH THE WELDER DEMONSTRATING UNDERSTANDING OF REQUIREMENTS AND POSSESSION OF SKILLS AND TOOLS TO VERIFY THESE ITEMS, THE PERFORM DESIGNATION OF THIS TASK SHALL BE REDUCED TO OBSERVE; AND THE WELDER SHALL PERFORM THIS TASK, SHALL BE REDUCED TO OBSERVE. THE CONTINUED PERFORMANCE OF THIS TASK, THE TASK SHALL BE RETURNED TO PERFORM UNTIL, SUCH TIME AS THE INSPECTOR HAS RE-ESTABLISHED ADEQUATE ASSURANCE THAT THE WELDER WILL PERFORM THE INSPECTION TASKS LISTED. AT MOMENT AND BRACED FRAMES WHERE R < 3, THE DESIGNATION SHOULD BE OBSERVE.
6. # - INDICATES SPECIAL INSPECTIONS REQUIRED FOR PROGRESSIVE COLLAPSE RESISTANCE.

STATEMENT OF SPECIAL INSPECTIONS AND STRUCTURAL TEST:

- | | | | |
|--|---|--------------------------|--------------------------|
| THIS SECTION APPLIES TO THE STRUCTURAL PORTIONS OF THE PROJECT REQUIRING SPECIAL INSPECTION. THE SPECIAL INSPECTOR'S DUTIES ARE AS DESCRIBED IN SECTION 1704.2 AND 1704.3 OF CBC COPIES OF TEST RESULTS AND FINAL REPORTS SHALL BE FURNISHED TO THIS ENGINEER IN ADDITION TO OTHER NORMAL DISTRIBUTIONS WITHIN ONE WEEK OF TEST OR INSPECTION. | | | |
| 2. | ALL TESTS AND INSPECTIONS SHALL BE PERFORMED BY AN INDEPENDENT TESTING AND INSPECTION AGENCY EMPLOYED BY THE OWNER OR ARCHITECT AND NOT THE CONTRACTOR PER CBC SECTION 1703. PROVIDING SPECIAL INSPECTION SHALL BE APPROVED BY THE STRUCTURAL ENGINEER OF RECORD. | | |
| 3. | THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE TEST AND INSPECTION FIRM WITH A SCHEDULE TO FACILITATE THE PROPER COORDINATION OF WORK. | | |
| 4. | PORTIONS OF WORK REQUIRING SPECIAL INSPECTION: | YES | NO |
| V. STRUCTURAL STEEL: | | | |
| | A. MILL REPORTS AND IDENTIFICATION OF STEEL (AFFIDAVIT OF COMPLIANCE)..... | ☐ | ☐ |
| | B. SAMPLING AND TESTING OF SPECIMENS..... | ☐ | ☐ |
| | C. SEE TABLES N5.4-1 THRU N5.4-3 AND TABLES N5.6-1 THRU N5.6-3 OF AISC 360 FOR ALL STRUCTURAL STEEL. | | |
| | D. SEE TABLES J8-1 THRU J6-3, TABLES J7-1 THRU J7-3 AND TABLE J8-1 OF AISC 341 FOR ALL SEISMIC RESISTING STRUCTURAL STEEL ELEMENTS IN SEISMIC DESIGN CATEGORY C,D,E AND F. | | |
| | E. SPECIAL INSPECTIONS AND QUALIFICATION OF WELDING SPECIAL INSPECTORS FOR COLD-FORMED STEEL FLOOR AND ROOF DECK SHALL BE IN ACCORDANCE WITH THE QUALITY ASSURANCE INSPECTION REQUIREMENTS OF SDI QA/QC. | | |
| | F. SPECIAL INSPECTIONS OF OPEN-WEB STEEL JOISTS AND JOIST GIRDERS SHALL BE IN ACCORDANCE WITH TABLE 1705.2.3 | | |
| VI. WELDING: | | | |
| | A. ALL STRUCTURAL WELDING (INCLUDES DECKING AND WELDED STUDS), EXCEPT WELDING IN APPROVED SHOPS PER CBC 1704.2.5.1..... | ☐ | ☐ |
| | B. ULTRASONIC TESTING OF FULL PENETRATION WELD CONNECTIONS AT MOMENT FRAMES, BRACED FRAMES, BEAM SPLICES, AND FIELD WELDS..... | ☐ | ☐ |
| | C. STRUCTURAL LIGHT GAGE METAL FRAME WELDING..... | ☐ | ☐ |
| | D. REINFORCING STEEL WELDING PER AISC 360 AND AISC 341..... | ☐ | ☐ |
| | E. SEE TABLES N5.4-1 THRU S5.4-3 OF AISC 360 FOR ANY ADDITIONAL REQUIRED VERIFICATION AND INSPECTION OF STEEL CONSTRUCTION. | | |
| | F. SEE TABLES J6-1 THRU J6-3 OF AISC 341 FOR ANY ADDITIONAL REQUIRED VERIFICATION AND INSPECTION OF WELDING FOR SEISMIC DESIGN CATEGORY C,D,E AND F. | | |
| VII. BOLTING: | | | |
| | A. HIGH STRENGTH BOLT A325SC AND A490SC (TORQUE VERIFICATION)..... | ☐ | ☐ |
| | B. HIGH STRENGTH BOLT A325N AND A490N (SNUG CONTACT OF PLYS)..... | ☐ | ☐ |
| | C. EXPANSION / ADHESIVE ANCHORS IN CONCRETE OR MASONRY..... | ☐ | ☐ |
| | D. ANCHOR RODS AT CONCRETE WALLS AND BRACED FRAMES, (BOLT INSTALLATION AND CONCRETE PLACEMENT)..... | ☐ | ☐ |
| | E. SEE TABLES N5.6-1 THRU N5.6-3 OF AISC 360 FOR ANY ADDITIONAL REQUIRED VERIFICATION AND INSPECTION OF STEEL CONSTRUCTION. | | |
| | F. SEE TABLES J7-1 THRU J7-3 OF AISC 341 FOR ANY ADDITIONAL REQUIRED VERIFICATION AND INSPECTION OF BOLTING FOR SEISMIC DESIGN CATEGORY C,D,E AND F. | | |
| VIII. INSULATING CONCRETE FILL: | | | |
| | TEST CYLINDERS AND INSPECTIONS. | ☐ | ☐ |
| 5. | APPROVED FABRICATOR: (MUST SUBMIT CERTIFICATE OF COMPLIANCE) FOR ALL OFFSITE FABRICATION SUCH AS STRUCTURAL STEEL, GLU-LAMS, PRECAST CONCRETE, ETC.. | ☐ | ☐ |
| 6. | STRUCTURAL OBSERVATIONS REQUIRED AS BY THIS ENGINEER OR THE BUILDING DEPARTMENT. THE OWNER SHALL EMPLOY AN ENGINEER APPROVED BY THIS ENGINEER TO PERFORM STRUCTURAL OBSERVATION AS DEFINED IN CBC SECTION 1704.6. | ☐ | ☐ |
| 7. | EACH CONTRACTOR OR SUB-CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A WIND OR SEISMIC FORCE RESISTING SYSTEM / COMPONENT LISTED IN THE STATEMENT OF SPECIAL INSPECTIONS SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND THE OWNER PRIOR TO THE COMMENCEMENT OF WORK ON SUCH SYSTEM OR COMPONENT. THE CONTRACTOR'S STATEMENT OF RESPONSIBILITY SHALL CONTAIN AN ACKNOWLEDGMENT OF AWARENESS OF THE SPECIAL REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTIONS. | | |

STRUCTURAL STEEL			
PRIOR TO WELDING (TABLE N5.4-1, AISC 360-22 AND TABLE J6.1, AISC 341-22)			
TASK	QC	QA	DESCRIPTION
1. VERIFY WELDING PROCEDURES (WPS) AND CONSUMABLE CERTIFICATES	P	O/P	(AISC 360 - TABLE N5.4-1)
2. MATERIAL IDENTIFICATION (TYPE/GRADE)	O	O	(AISC 360 - TABLE N5.4-1 AND AISC 341 - TABLE J6-1)
3. WELDER IDENTIFICATION SYSTEM	O	O	A SYSTEM SHALL BE MAINTAINED BY WHICH A WELDER WHO HAS WELDED A JOINT OR MEMBER CAN BE IDENTIFIED. STIMPS, IF USED, SHALL BE THE LOW-STRESS DYE TYPE. (AISC 360 - TABLE N5.4-1 AND AISC 341 - TABLE J6-1)
4. FIT-UP GROOVE WELDS (INCLUDING JOINT GEOMETRY)	O/P****	O	JOINT PREPARATION DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL) CLEANLINESS (CONDITION OF STEEL SURFACES) TACKING (TACK WELD QUALITY AND LOCATION) BACKING TYPE AND FIT (IF APPLICABLE) (AISC 360 - TABLE N5.4-1 AND AISC 341 - TABLE J6-1)
5. FIT-UP C/P GROOVE WELDS (INCLUDING JOINT GEOMETRY)	P	O	JOINT PREPARATION DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL) CLEANLINESS (CONDITION OF STEEL SURFACES) TACKING (TACK WELD QUALITY AND LOCATION) BACKING TYPE AND FIT (IF APPLICABLE) (AISC 360 - TABLE N5.4-1)
6. CONFIGURATION AND FINISH OF ACCESS HOLES	O	O	(AISC 360 - TABLE N5.4-1 AND AISC 341 - TABLE J6-1)
7. FIT-UP OF FILLET WELDS	O/P****	O	DIMENSIONS (ALIGNMENT, GAPS AT ROOT) CLEANLINESS (CONDITION OF STEEL SURFACES) TACKING (TACK WELD QUALITY AND LOCATION) (AISC 360 - TABLE N5.4-1 AND AISC 341 - TABLE J6-1)
8. CHECK WELDING EQUIPMENT	O	-	(AISC 360 - TABLE N5.4-1)
DURING WELDING (TABLE N5.4-2, AISC 360-22 AND TABLE J6.2, AISC 341-22)			
TASK	QC	QA	DESCRIPTION
1. USE OF QUALIFIED WELDERS	O	O	(AISC 360 - TABLE N5.4-2) (AISC 341 - TABLE J6-2)
2. CONTROL AND HANDLING OF WELDING CONSUMABLES	O	O	PACKAGING EXPOSURE CONTROL (AISC 360 - TABLE N5.4-2 AND AISC 341 - TABLE J6-2)
3. NO WELDING OVER CRACKED TACK WELDS	O	O	(AISC 360 - TABLE N5.4-2 AND AISC 341 - TABLE J6-2)
4. ENVIRONMENTAL CONDITIONS	O	O	WIND SPEED WITHIN LIMITS PRECIPITATION AND TEMPERATURE (AISC 360 - TABLE N5.4-2 AND AISC 341 - TABLE J6-2)
5. WELDING PROCEDURE SPECIFICATIONS (WPS) FOLLOWED	O	O	SETTINGS ON WELDING EQUIPMENT TRAVEL SPEED SELECTED WELDING MATERIALS SHIELDING GAS TYPE/FLOW RATE PREHEAT APPLIED INTERPASS TEMPERATURE MAINTAINED (MIN,MAX) PROPER POSITION (F, V, H, OH) INTERMIX OF FILLER METALS AVOIDED UNLESS APPROVED (AISC 360 - TABLE N5.4-2 AND AISC 341 - TABLE J6-2)
6. WELDING TECHNIQUES	O	O	INTERPASS AND FINAL CLEANING EACH PASS WITHIN PROFILE LIMITATIONS EACH PASS MEETS QUALITY REQUIREMENTS (AISC 360 - TABLE N5.4-2 AND AISC 341 - TABLE J6-2)
7. PLACEMENT AND INSTALLATION OF STEEL HEADED STUD ANCHORS	P	P	(AISC 360 - TABLE N5.4-2)
AFTER WELDING (TABLE N5.4-3, AISC 360-22 AND TABLE J6.3, AISC 341-22)			
TASK	QC	QA	DESCRIPTION
1. WELDS CLEANED	O	O	(AISC 360 - TABLE N5.4-3 AND AISC 341 - TABLE J6-3)
2. SIZE, LENGTH, AND LOCATION OF WELDS	P	P	(AISC 360 - TABLE N5.4-3 AND AISC 341 - TABLE J6-3)
3. WELDS MEET VISUAL ACCEPTANCE CRITERIA	P/D****	P/D****	CRACK PROHIBITION WELD/DIAPHRAGM METAL FUSION CRATER CROSS SECTION WELD PROFILES WELD SIZE UNDERCUT POROSITY (AISC 360 - TABLE N5.4-3 AND AISC 341 - TABLE J6-3)
4. ARC STRIKES	P	P	(AISC 360 - TABLE N5.4-3)
5. INSPECT K-AREA FOR CRACKS WITHIN 3" OF THE WELD WHEN WELDING OF DOUBLER PLATES, CONTINUITY PLATES OR STIFFENERS OCCURRED	P/D****	P/D****	WHEN WELDING OF DOUBLER PLATES, CONTINUITY PLATES OR STIFFENERS HAS BEEN PERFORMED IN THE K-AREA, VISUALLY INSPECT THE WEB K-AREA FOR CRACKS WITHIN 3 IN. OF THE WELD. (AISC 360 - TABLE N5.4-3)
6. CRACKS AT WELD ACCESS HOLES IN ROLLED SHAPES (SEE AISC 360 SECTION A3.1C) AND BUILT-UP HEAVY SHAPES (SEE AISC 360 SECTION A3.1D)	P	P/D****	(AISC 360 - TABLE N5.4-3)
7. BACKING REMOVED, WELD TABS REMOVED AND FINISHED, AND FILLET WELDS ADDED (IF REQUIRED)	P/D****	P/D****	(AISC 360 - TABLE N5.4-3) (AISC 341 - TABLE J6-3)
8. PLACEMENT OF REINFORCING OR CONTOURING FILLET WELDS (IF REQUIRED)	P/D****	P/D****	(AISC 341 - TABLE J6-3)
9. REPAIR ACTIVITIES	P	P/D****	(AISC 360 - TABLE N5.4-3 AND AISC 341 - TABLE J6-3)
10. DOCUMENT ACCEPTANCE OR REJECTION OF WELDED JOINT/MEMBER	P	P	(AISC 360 - TABLE N5.4-3)
11. NO PROHIBITED WELDS HAVE BEEN ADDED WITHOUT THE APPROVAL OF THE EOR	O	O	(AISC 360 - TABLE N5.4-2)

OTHER STEEL INSPECTIONS (SECTION N5.8, AISC 360-22)			
TASK	QC	QA	DESCRIPTION
1. FABRICATED STEEL OR ERECTED STEEL FRAME	.	0	VERIFY COMPLIANCE WITH THE DETAILS SHOWN ON THE CONSTRUCTION DOCUMENTS, SUCH AS BRACES, STIFFENERS, MEMBER LOCATIONS AND PROPER APPLICATION OF JOINT DETAILS AT EACH CONNECTION. (AISC 360 N5.7)



REVISIONS		
No.	Description	Date

ALPER ■ AUDI
STRUCTURAL ENGINEERS

6 Cityplace Drive Suite 1025 | St. Louis, MO 63141
phone 314.432.8800 | www.alperaudi.com

ULTA BEAUTY WAREHOUSE

850 EAST CENTRAL AVE
FRESNO, CA 93706

Sheet Name:

Sheet Name: GENERAL NOTES

Project Number: 25093

Date: 11/20/2025

Drawn By: DMM

Checked By: MCL

Sheet Number:

S0.01